



August 5, 2010

**ADDENDUM NO. 1**

To become part of the Bidding Documents for the project:

**SPRINKLER AND HVAC RENOVATIONS  
JORDAN FIRE STATION  
89 ROPE FERRY ROAD  
WATERFORD, CT  
BID NO. 11-102**

1. Please acknowledge receipt of this Addendum in your Bid Form. Interpretations, corrections and changes of the bidding documents made in a manner other than by Addendum will not be binding and bidders shall not rely upon them.
2. ADDENDUMS will be issued only to those Contractors present at the 07/26/2010 Mandatory Pre-Bid Meeting and only those Contractors attending this walk-through may submit a Bid on the project. It is the responsibility of Contractors bidding the Project to distribute copies of this Addendum to all subcontractors, suppliers and other entities providing quotations.

**PROJECT MANUAL/SPECIFICATIONS:**

**Bid Form – Page C-2:**

3. CLARIFICATION FOR UNIT PRICE #1: Contractor shall paint ceiling to match existing color/texture. If the patch is of poor quality and does not match reasonably in the opinion of the Owner and Architect, the entire ceiling shall be repainted. If the existing holes are bigger then there would be two choices: 1) Install larger escutcheon plates or 2) infill and patch the holes as described in the Project Manual: Section 017329 – Cutting and Patching, Section 092900 – Gypsum Board Assemblies, and 099123 – Interior Painting.

**DRAWINGS:**

**Drawing FP-3:**

4. ADD to second to last sentence in Fire Protection Section 3.5 TESTS: "Flushing shall be in accordance with NFPA 13 or NFPA 25."

**Drawing M-1:**

5. First Floor Plan: Contractor shall relocate CU-1 and DCU-A further south along west side of building, maintaining 10 feet minimum separation from existing propane tank, extending refrigerant lines accordingly and removing existing plant material as required.

\*\*\*\*\*END OF ADDENDUM NO. 1\*\*\*\*\*